



NOTES:

1. TRANSVERSE SAWED CONTRACTION JOINTS AT 15' INTERVALS AND LONGITUDINAL SAWED CONTRACTION JOINTS 12' FROM OUTSIDE BACK OF CURBS.
- \* 2. LIME SHALL BE APPLIED AT 6% BY WEIGHT MINIMUM QUANTITY IS 36#/SY. IN SOME AREAS A GREATER QUANTITY (OR A LIME SERIES TEST) MAY BE REQUIRED AT THE CITY'S DISCRETION.
- \*\* 3. CEMENT SHALL BE APPLIED AT 5% BY WEIGHT. MINIMUM QUANTITY IS 36#/SY.

REVISIONS	
Revised 11/16/99 (Bar Sizes & Pavement Layer Thicknesses)	
CITY OF ARLINGTON, TEXAS	
PROJECT NUMBER	
PROJECT NAME	
( PROJECT LIMITS )	
DATE:	SCALE: SHEET OF
DRAWN BY:	CHECKED BY: