



28' H.M.A.C. RURAL SECTION  
 TYPICAL CROSS SECTION  
 NTS

- NOTES: \* 1. LIME SHALL BE APPLIED AT 6 % BY WEIGHT. MINIMUM QUANTITY IS 54#/SY. IN SOME AREAS A GREATER QUANTITY (OR A LIME SERIES TEST) MAY BE REQUIRED AT THE CITY'S DISCRETION.
2. BAR DITCH SIDE SLOPE VARIES DEPENDING UPON DESIGN. NO GREATER THAN 3:1 WITHOUT ARMORING.
3. FOR 30" GUTTER DETAIL, SEE CURB & GUTTER DETAILS.
- \*\* 4. CEMENT SHALL BE APPLIED AT 5% BY WEIGHT. MINIMUM QUANTITY IS 45#/SY.

APPROVED	DATE	SCALE	DATE
	11/16/20	AS SHOWN	11/16/20
CITY OF ARLINGTON, TEXAS			
PROJECT NUMBER			
PROJECT NAME			
(PROJECT LIMITS)			
DESIGNED BY	CHECKED BY	DATE	DATE