



38' CONCRETE PAVEMENT SECTION
TYPICAL CROSS SECTION

NTS

- NOTES:
1. TRANSVERSE SAWED CONTRACTION JOINTS AT 15' INTERVALS FOR CONCRETE PAVEMENT.
 - * 2. LIME SHALL BE APPLIED AT 6% BY WEIGHT MINIMUM QUANTITY IS 36#/SY. IN SOME AREAS A GREATER QUANTITY (OR A LIME SERIES TEST) MAY BE REQUIRED AT THE CITY'S DISCRETION.
 - * * 3. CEMENT SHALL BE APPLIED AT 5% BY WEIGHT. MINIMUM QUANTITY IS 30#/SY.

CITY OF ARLINGTON, TEXAS	
PROJECT NUMBER PROJECT NAME (PROJECT LIMITS)	
DATE: _____ PREPARED BY: _____	SCALE: _____ DRAWN BY: _____
SHEET: _____ OF _____ REVISIONS: _____	CHECKED BY: _____ APPROVED BY: _____