


56' CONCRETE PAVEMENT SECTION
TYPICAL CROSS SECTION
NTS

- NOTES:
1. TRANSVERSE SAWED CONTRACTION JOINTS AT 15' INTERVALS & LONGITUDINAL SAWED CONTRACTION JOINTS AT 11' INTERVALS FOR CONCRETE PAVEMENT.
 - * 2. LIME SHALL BE APPLIED AT 6% BY WEIGHT MINIMUM QUANTITY IS 36#/SY. IN SOME AREAS A GREATER QUANTITY (OR A LIME SERIES TEST) MAY BE REQUIRED AT THE CITY'S DISCRETION.
 - ** 3. CEMENT SHALL BE APPLIED AT 5% BY WEIGHT. MINIMUM QUANTITY IS 30#/SY.

<div>  <div> <div>CITY OF ARLINGTON, TEXAS</div> <div>PROJECT NUMBER</div> <div>PROJECT NAME</div> <div>(PROJECT LIMITS)</div> </div> </div>		<div> <div>REVISIONS</div> <div>Revised 11/16/09 (See Also: & Amendment Log: 2/10/2010)</div> </div>	
DATE	SCALE	REVISION	OF
APPROVED BY:	ISSUED BY:	CHANGED BY:	