

NOTES:

- 1. TRANSVERSE SAWED CONTRACTION JOINTS AT 15' INTERVALS AND LONGITUDINAL SAWED CONTRACTION JOINTS 12' FROM OUTSIDE BACK OF CURBS.
- * 2. LIME SHALL BE APPLIED AT 6% BY WEIGHT MINIMUM QUANTITY IS 36#/SY. IN SOME AREAS A GREATER QUANTITY (OR A LIME SERIES TEST) MAY BE REQUIRED AT THE CITY'S DISCRETION.
- ** 3. CEMENT SHALL BE APPLIED AT 5% BY WEIGHT. MINIMUM QUANTITY IS 36#/SY.

CITY OF ARLINGTON, TEXAS						
PROJECT NUMBER						
PROJECT NAME						
(PROJECT LIMITS)						
DATE:			CALE:		SHEET	OF
DESIGNED	nv.	i,	RAWN BY:		CHECKED	RY.