

**Storm Water  
Project Rankings  
September 2007**

Location	List Year	Total Score	Concept. Design (000s)	Detail Design (000s)	Construction (000s)	Project Description	# Houses Flooded
Green Meadows Addition	2001	80	\$ 75	\$ 120	\$ 400	upsized channel/flume or run parallel system	5
2222 Lincoln	2004	70	\$ 20	\$ 30	\$ 100	construct wall adjacent to channel to force flow to parking lot	5
2116 Greencove	2002	68	\$ 15	\$ 30	\$ 61	grading behind lots, extend system and upgrade inlets/pipe	4
Shady Park Drive	2001	63	\$ 20	\$ 30	\$ 109	extend system from San Rafael	4
2206 Wesley Dr	2005	62	\$ 15	\$ 20	\$ 75	construct inlet and pipe	1
1230 Dan Gould	2001	60	\$ 10	\$ 15	\$ 40	extend system from Cooper St to Turner Warnell	1
1503 Goliad	2002	60	\$ 20	\$ 35	\$ 183	extend upstream and upgrade existing pipe system	4
2308 Miguel Lane	2007	60	\$ 15	\$ 20	\$ 58	extend system up Lindblad to Dennis	7
6637 Townlake circle	2004	59	\$ 10	\$ 15	\$ 25	install inlets and pipe	1
5905 Arbor Valley/Perkins	2007	59	\$ 10	\$ 15	\$ 25	upsized pipe from low pt inlets to main	4
1001 McKinney/710 Ross	2000	58	\$ 25	\$ 55	\$ 346	upgrade system on Ross/Cedar and line channel along McKinney	3
2300 Southcrest	2004	58	\$ 10	\$ 15	\$ 40	construct parallel inlet box	1
1400/1412 Country Club	2007	57	\$ 10	\$ 15	\$ 24	construct wall and add positive overflow at low point	3
Del Mar/Matthews Ct	2007	57	\$ 15	\$ 20	\$ 101	add system in Fielder Road	8
7408 & 7501 Willow Oak	1995	56	\$ 20	\$ 20	\$ 100	regrade bar ditches and upsized driveway culverts	2

921 Web Street	2001	55	\$ 10	\$ 15	\$ 20	construct system to Randol Mill	1
Willow Bend/Thousand Oaks	2003	55	\$ 15	\$ 20	\$ 95	3 areas - extend systems upstream	3
2803 Sequoia	2007	55	\$ 10	\$ 15	\$ 47	add flume at rear of lots, drop inlet and pipe system	5
3215 Collard Road	2002	54	\$ 10	\$ 15	\$ 25	regrade bar ditches/upsized driveway culverts & realign outfall	1
4218 Southcrest	1999	53	\$ 10	\$ 10	\$ 10	construct swale/berm on school prop, install flume to street	1
2610 Fall Creek	2001	53	\$ 10	\$ 15	\$ 25	upgrade existing system	1
2311 Royce/Chimney Court	2006	53	\$ 20	\$ 35	\$ 225	line channel/install pipe\install parallel system and drop inlets	5
5312 Little Creek Ct	2007	53	\$ 15	\$ 20	\$ 54	add inlets/pipe on Aurora	3
3609 Danbury	2001	52	\$ 15	\$ 20	\$ 90	upsized system and reconfigure Mayfield culverts	2
2011 N. Meadow Way Circle	2004	52	\$ 10	\$ 10	\$ 12	upsized inlets and add overflow flume	1
2307 Medlin	2000	50	\$ 10	\$ 15	\$ 50	upsized existing storm sewer lateral	1
2034 Fleur De Lis Ct	2007	50	\$ 5	\$ 5	\$ 3	rebuild drive approaches	2
2710 Wolff Drive	1999	49	\$ 20	\$ 25	\$ 150	construct inlet and pipe	5
Pleasant Forest	2001	49	\$ 15	\$ 20	\$ 65	extend existing system to IH20	2
3401 Sheffield Drive	2002	49	\$ 10	\$ 15	\$ 40	construct low point inlets/upsized pipe and add overflow flume	1
4612 Willow Bend	2005	48	\$ 10	\$ 15	\$ 25	construct flume to creek	1
2703 W. Division	1994	46	\$ 5	\$ 5	\$ 12	reconstruct driveway	1
600 Matthews Drive	2004	45	\$ 20	\$ 25	\$ 150	construct new system down Matthews to Sanford	1

1004 W. Fourth Street	2001	43	\$ 20	\$ 45	\$ 300	upsized existing box culvert	1
802 Delia Ct	2006	43	\$ 10	\$ 15	\$ 41	extend system into backyards	1
2800 Canongate	2007	43	\$ 15	\$ 20	\$ 61	upgrade inlets/pipe, extend system upstream	2
3810 Marine Ct	2007	43	\$ 5	\$ 5	\$ 5	construct berm to keep water in street	1
1404 Briarwood	1999	42	\$ 10	\$ 15	\$ 45	rework roadway crown and reconstruct drive approach	1
2507 Smouldering Wood	2007	40	\$ 15	\$ 20	\$ 73	add inlets to capture water before leaving street	2
2009 Botts	2007	40	\$ 15	\$ 15	\$ 33	construct wall to keep water in Cooper Street/upsized inlets (analyze Cooper St system)	2
3904 Wrentham	2007	39	\$ 5	\$ 5	\$ 7	add flume along property lines	1
706 N. Davis/1205 W Sanford	2007	38	\$ 10	\$ 10	\$ 15	add inlet on Sanford/rebuild dw	1
3114 Woodford Dr	2007	36	\$ 10	\$ 10	\$ 12	upsized inlet and add overflow flume	1
2115 Valleydale	2007	35	\$ 10	\$ 15	\$ 45	upsized pipe/inlets to capture 100 yr	2
2307 Briarwood	2007	29	\$ 10	\$ 15	\$ 30	add inlets/pipe to existing system	1
2806 Marquis Cr East	2007	26	\$ 20	\$ 25	\$ 139	install new system from Perkins	1
1001 N Bowen Road	1995	20	\$ 10	\$ 15	\$ 50	construct concrete channel block wall to mitigate erosion	
4801 Bonneville	2007	20	\$ 15	\$ 20	\$ 90	extend drainage system	1